QUOTATION · ELEVATION WORKS

Project	**External Elevation Works – Compound**	Quotation No.	**000295**
Location	**Riyadh, Kingdom of Saudi Arabia**	Date	**11 November 2026**
Basis	**Supply & install · re-measurable**	Validity	**15 days**
Reference	**BoQ · Drawing A-209 · Project 26-061**	Prepared by	**Engr. Talha Niaz**

01 · Price Summary

CURRENCY: SAR

Supply and installation of the external elevation works, priced from the CAD-verified Bill of Quantities. Item-by-item detail is in Section 03.

No.	Section	Main quantities	Amount (SAR)
01	**North Elevation**	Travertine 119 m² · Louvers 20 m² · Cladding 8 m² · Windows 12 m²	26,450.00
02	**South Elevation**	Travertine 119 m² · Louvers 20 m² · Cladding 8 m² · Windows 12 m²	26,450.00
03	**East Elevation**	Travertine 180 m² · Louvers 25 m² · Cladding 5.4 m²	33,080.00
04	**West Elevation**	Travertine 180 m² · Louvers 25 m² · Cladding 5.4 m²	33,080.00
05	**General Items & Accessories**	Scaffolding · Sealants & trims 320 lm · Cleaning & handover	17,900.00

Travertine Cladding **598 m²**

Total (Ex-VAT) **SAR 136,960.00**

One hundred thirty-six thousand nine hundred sixty Saudi Riyals only, exclusive of VAT.

02 · Scope of Works

6 WORK PACKAGES

01 Travertine Cladding
60×90 cm tiles, 10 mm groove, dry-fix stainless anchors and adhesive on a prepared substrate.

02 Black Cladding Bands
Matte black solid panels as 20 cm parapet bands on an aluminium carrier.

03 WPC/PVC Louvers
Vertical walnut-finish louvers on powder-coated aluminium rails.

04 Aluminium Windows
Black, double glazed, thermally broken frames with sills and hardware.

05 Sealants & Trims
Colour-matched silicone, expansion joints and aluminium edge trims.

06 Access & Handover
Scaffolding and protection, final cleaning, touch-up and handover.

المملكة العربية السعودية - الرياض - القادسية - جوال: ٠٥٣٣٣٩٣٣٩٧
Kingdom of Saudi Arabia - Riyadh - Al-Qadisiyah - Mobile: 0533393397

03 · Detailed Bill of Quantities

SUPPLY & INSTALL

Item	Description	Unit	Qty	Rate	Amount (SAR)
A	**North Elevation**				
A.1	Travertine Tile Cladding 60×90 cm Dry-fix stainless anchors + adhesive, 5% wastage incl.	m²	119.00	150.00	17,850.00
A.2	Black Solid Cladding Panels, 20 cm band Matte black, powder-coated aluminium carrier	m²	8.00	200.00	1,600.00
A.3	Exterior WPC/PVC Vertical Louvers, walnut On aluminium rails, UV & weather resistant	m²	20.00	200.00	4,000.00
A.4	Black Aluminium Windows, double glazed Powder-coated, thermally broken frames, complete	m²	12.00	250.00	3,000.00
	Subtotal – North Elevation				**26,450.00**
B	**South Elevation**				
B.1	Travertine Tile Cladding 60×90 cm Dry-fix stainless anchors + adhesive, 5% wastage incl.	m²	119.00	150.00	17,850.00
B.2	Black Solid Cladding Panels, 20 cm band Matte black, powder-coated aluminium carrier	m²	8.00	200.00	1,600.00
B.3	Exterior WPC/PVC Vertical Louvers, walnut On aluminium rails, UV & weather resistant	m²	20.00	200.00	4,000.00
B.4	Black Aluminium Windows, double glazed Powder-coated, thermally broken frames, complete	m²	12.00	250.00	3,000.00
	Subtotal – South Elevation				**26,450.00**
C	**East Elevation**				
C.1	Travertine Tile Cladding 60×90 cm Dry-fix stainless anchors + adhesive, 5% wastage incl.	m²	180.00	150.00	27,000.00
C.2	Black Solid Cladding Panels, 20 cm band Matte black, powder-coated aluminium carrier	m²	5.40	200.00	1,080.00
C.3	Exterior WPC/PVC Vertical Louvers, walnut On aluminium rails, UV & weather resistant	m²	25.00	200.00	5,000.00
	Subtotal – East Elevation				**33,080.00**

Continued on the next page: West Elevation, General Items and the grand total.

المملكة العربية السعودية - الرياض - القادسية - جوال: ٠٥٣٣٣٩٣٣٩٧
Kingdom of Saudi Arabia - Riyadh - Al-Qadisiyah - Mobile: 0533393397

03 · Detailed Bill of Quantities (continued)

SUPPLY & INSTALL

Item	Description	Unit	Qty	Rate	Amount (SAR)
D	**West Elevation**				
D.1	Travertine Tile Cladding 60×90 cm Dry-fix stainless anchors + adhesive, 5% wastage incl.	m²	180.00	150.00	27,000.00
D.2	Black Solid Cladding Panels, 20 cm band Matte black, powder-coated aluminium carrier	m²	5.40	200.00	1,080.00
D.3	Exterior WPC/PVC Vertical Louvers, walnut On aluminium rails, UV & weather resistant	m²	25.00	200.00	5,000.00
	Subtotal – West Elevation				**33,080.00**
E	**General Items & Accessories**				
E.1	Scaffolding, access & protection Full perimeter, erect & dismantle as per sequence	ls	1.00	8,000.00	8,000.00
E.2	Waterproofing membrane Optional, priced separately below	—	—	—	Excluded
E.3	Joint sealants, expansion joints & edge trims Colour-matched silicone and aluminium trims	lm	320.00	20.00	6,400.00
E.4	Cleaning, protection & handover Final clean and touch-up of all surfaces	ls	1.00	3,500.00	3,500.00
	Subtotal – General Items & Accessories				**17,900.00**
	Grand Total – External Elevation Works (Ex-VAT)				**136,960.00**

Optional item · not included in the total

E.2a Waterproofing membrane and substrate preparation for all cladding areas — **598.00 m² × 65.00 = SAR 38,870.00**

Liquid-applied or bituminous; can be omitted if the substrate is already protected. To be confirmed by the client.

Total including the optional waterproofing (Ex-VAT) — **SAR 175,830.00**

المملكة العربية السعودية - الرياض - القادسية - جوال: ٠٥٣٣٣٩٣٣٩٧
Kingdom of Saudi Arabia - Riyadh - Al-Qadisiyah - Mobile: 0533393397

QUOTATION · ELEVATION WORKS

04 · Payment Schedule

TOTAL: SAR 136,960.00

The total is payable in four instalments, each due on reaching the milestone below.

No.	Milestone	Share	Amount (SAR)
01	Advance payment on signing	30%	41,088.00
02	On delivery of materials to site	30%	41,088.00
03	On completion of cladding & louver installation	30%	41,088.00
04	On final handover	10%	13,696.00
	Total	100%	136,960.00

Amounts are exclusive of VAT. If the optional waterproofing is added, each instalment is recalculated on the revised total.

05 · Commercial Notes

Scope — Supply and installation of the works listed in Section 03 for the North, South, East and West elevations, as per Drawing A-209.

Quantities — Re-measurable. Quantities are taken from the CAD-verified BoQ; the final amount is adjusted to the measured site survey and approved shop drawings at the unit rates above.

Payment — Payable in instalments as per the payment schedule in Section 04. Work starts once the advance payment is received.

VAT — Amounts above are exclusive of VAT, if applicable. VAT will be charged in accordance with applicable Saudi regulations and the supplier's VAT registration status.

Exclusions — Waterproofing (optional item), structural or substrate repairs, permits and authority fees, and any works not listed in Section 03.

Warranty — 12-month defects liability period from the date of handover.

Validity — This quotation is valid for 15 days from the quotation date.

06 · Acceptance

For the Client

Name _____

Signature _____

Date _____

For Max Design

Name _____

Signature _____

Date _____

المملكة العربية السعودية - الرياض - القادسية - جوال: ٠٥٣٣٣٩٣٣٩٧
Kingdom of Saudi Arabia - Riyadh - Al-Qadisiyah - Mobile: 0533393397