MAX DESIGN

BILL OF QUANTITIES – EXTERNAL ELEVATION WORKS (CAD VERIFIED)

Compound Elevation Design | Project No. 26-061 | Drawing A-209 | Prepared from ELEVATION.dwg

Prepared by: Engr. Talha Niaz | Consultant: MAX Design | Date: 09 November 2026 | Riyadh, KSA

CAD VERIFICATION NOTES

1. Quantities taken directly from explicit area labels embedded in ELEVATION.dwg (AC1032). These supersede any earlier estimates derived from PDF dimensions alone.
2. Travertine: 119 m² (×2) + 180 m² (×2) = 598 m² total. PVC Louvers: 20 m² (×2) + 25 m² (×2) = 90 m² total. Black cladding: 20 cm high bands, lengths 40 m (×2) + 27 m (×2) = 26.8 m².
3. Windows: 12 m² labeled (×2). Remaining openings on East/West elevations included within the cladding net areas as per CAD.
4. Methodology: Travertine 60×90 cm with 10 mm groove – dry-fix stainless steel anchors + adhesive on waterproofed substrate. Black cladding & louvers on powder-coated aluminium carrier systems. All works include scaffolding, protection, cleaning and 12-month DLP.
5. Rates are indicative KSA (Riyadh) market rates for supply & install, November 2026, exclusive of VAT. Subject to final shop drawings and site measure.

Item	Description	Unit	Qty	Unit Rate	Amount (SAR)	CAD Source	Methodology
A. NORTH ELEVATION (CAD: Travertine 119 m² | Louvers 20 m² | Cladding length 40 m)							
A.1	Travertine Tile Cladding 60×90 cm	m²	119.00	150.00	17,850.00	CAD: TRAVERTINE AREA 119 sqm	adhesive on prepared substrate. 5% wastage included.
A.2	Black Solid Cladding Panels (matte black) – 20 cm high parapet/top band, including aluminium substructure and concealed fixings.	m²	8.00	200.00	1,600.00	CAD: CLADDING 20 cm, LENGTH 40 m → 8.0 m²	Powder-coated Alu carrier system.
A.3	Exterior WPC/PVC Vertical Louvers, Walnut finish (LEO series type, 219 mm width), including aluminium carrier system and end caps.	m²	20.00	200.00	4,000.00	CAD: PVC LOUVER AREA 20 sqm	UV & weather resistant.
A.4	Black Aluminium Windows, powder-coated, double glazed, including frames, sills, sealants and hardware.	m²	12.00	250.00	3,000.00	CAD: WINDOW AREA 12 sqm	Thermally broken frames.
Subtotal – North Elevation					**26,450.00**		
B. SOUTH ELEVATION (CAD: Travertine 119 m² | Louvers 20 m² | Cladding length 40 m)							
B.1	Travertine Tile Cladding 60×90 cm	m²	119.00	150.00	17,850.00	CAD: TRAVERTINE AREA 119 sqm	adhesive on prepared substrate. 5% wastage included.
B.2	Black Solid Cladding Panels – 20 cm high parapet band.	m²	8.00	200.00	1,600.00	CAD: CLADDING 20 cm, LENGTH 40 m → 8.0 m²	Alu substructure.
B.3	Exterior WPC/PVC Vertical Louvers, Walnut finish, complete.	m²	20.00	200.00	4,000.00	CAD: PVC LOUVER AREA 20 sqm	Alu carrier system.
B.4	Black Aluminium Windows, complete.	m²	12.00	250.00	3,000.00	CAD: WINDOW AREA 12 sqm	Double glazed, powder coated.
Subtotal – South Elevation					**26,450.00**		
C. EAST ELEVATION (CAD: Travertine 180 m² | Louvers 25 m² | Cladding length 27 m)							
C.1	Travertine Tile Cladding 60×90 cm	m²	180.00	150.00	27,000.00	CAD: TRAVERTINE AREA 180 sqm	adhesive on prepared substrate. 5% wastage included.
C.2	Black Solid Cladding Panels – 20 cm high parapet band.	m²	5.40	200.00	1,080.00	CAD: CLADDING 20 cm, LENGTH 27 m → 5.4 m²	Alu substructure.
C.3	Exterior WPC/PVC Vertical Louvers, Walnut finish.	m²	25.00	200.00	5,000.00	CAD: PVC LOUVER AREA 25 sqm	Complete system.
Subtotal – East Elevation					**33,080.00**		
D. WEST ELEVATION (CAD: Travertine 180 m² | Louvers 25 m² | Cladding length 27 m)							
D.1	Travertine Tile Cladding 60×90 cm	m²	180.00	150.00	27,000.00	CAD: TRAVERTINE AREA 180 sqm	adhesive on prepared substrate. 5% wastage included.

D.2	Black Solid Cladding Panels – 20 cm high parapet band.	m²	5.40	200.00	1,080.00	CAD: CLADDING 20 cm, LENGTH 27 m → 5.4 m²	Alu substructure.
D.3	Exterior WPC/PVC Vertical Louvers, Walnut finish.	m²	25.00	200.00	5,000.00	CAD: PVC LOUVER AREA 25 sqm	Complete system.
Subtotal – West Elevation					**33,080.00**		
E. GENERAL ITEMS & ACCESSORIES (All Elevations)							
E.1	Scaffolding, access and protection for all elevation works (full perimeter).	ls	1.00	8,000.00	8,000.00	Provisional – based on overall extent	Erect and dismantle as per sequence.
E.2	Waterproofing membrane (OPTIONAL – see separate sum below)	m²	0.00	0.00	0.00	Based on total cladding area + margin	Full coverage before cladding.
E.3	Joint sealants, expansion joints and edge trims (all materials).	lm	320.00	20.00	6,400.00	Provisional	Colour-matched silicone and aluminium trims.
E.4	Cleaning, protection and handover of completed elevations.	ls	1.00	3,500.00	3,500.00	Final clean and touch-up	Include for all surfaces.
Subtotal – General Items					**17,900.00**		

GRAND TOTAL – EXTERNAL ELEVATION WORKS (Ex-VAT)	**136,960.00**

This BoQ is based on explicit area take-offs extracted from ELEVATION.dwg. All quantities are as labeled by the designer (Engr. Talha Niaz / MAX Design). Rates are indicative only and exclude VAT. Subject to final measured survey and approved shop drawings.

OPTIONAL ITEM (NOT INCLUDED IN TOTAL)

E.2a	Waterproofing membrane and substrate preparation for all cladding areas (	m²	598.00	65.00	**38,870.00**	Optional – can be omitted if subst	Liquid applied or bituminous. To be confirmed by client.

Note: Main Grand Total excludes waterproofing and any contingency/margin. Rates are direct supply & install only.